



Leath

Commission Order No. 2018-178
Second Quarter Term 2018

COMMISSION ORDER

STATE OF MISSOURI }
County of Franklin } ss.

Tuesday, May, 01, 2018
Contract/Agreements

IN THE MATTER OF APPROVING AND AUTHORIZING EXECUTION OF A CONTRACTUAL AGREEMENT WITH GERSHENSON CONSTRUCTION

WHEREAS, prior hereto in the manner required by Missouri law Franklin County solicited bids for the Possum Hollow Bridge Project; and

WHEREAS, MoDOT, after reviewing the bids received, concurs with the recommendation to award the Possum Hollow Bridge Project to Gershenson Construction, Inc. with a low bid in the total amount of \$491,841.50; and

WHEREAS, attached hereto is a copy of said bid.

IT IS THEREFORE ORDERED that the bid from Gershenson Construction, Inc. is hereby approved and that the Presiding Commissioner of Franklin County, is authorized to execute said Agreement on behalf of Franklin County.

IT IS FURTHER ORDERED that an executed copy of this Order be provided to Gershenson Construction, Inc.; Ron J. Williams, Highway Administrator; and Lynne Maloney, Accounts Payable.

I hereby certify that there is a balance otherwise unencumbered to the credit of the current year appropriation to which this order is chargeable and a cash balance otherwise unencumbered in the treasury to the credit of the fund which payment is to be made, each sufficient to meet this obligation.

Auditor *Lynne Maloney* 5-1-18

[Signature]
Presiding Commissioner

[Signature]
Commissioner of 1st District

Commissioner of 2nd District

ITEMIZED BID: The bidder should complete the following section. The bidder proposes to furnish all labor, materials, equipment, services, etc. required for the performance and completion of the work, as follows:

ITEMIZED BID FORM – STP 9901(626) Possum Hollow Bridge Replacement

Line	Pay Item #	Description	Units	Quantity	Unit Price	Total
10	2022010	REMOVAL OF IMPROVEMENTS	L.S.	1	14,000.00	14,000.00
20	2031000	CLASS A EXCAVATION	C.Y.	590	22.00	12,980.00
30	2036000	COMPACTING EMBANKMENT	C.Y.	160	14.00	2,240.00
70	3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	S.Y.	1,166	7.00	8,162.00
80	3101003	GRAVEL (A)	S.Y.	7	65.00	455.00
90	4011209	"BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)"	TON	204.6	110.00	22,506.00
100	4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	TON	290.3	95.00	27,578.50
110	4071005	TACK COAT	GAL	120	5.00	600.00
130	6115010A	LIGHT STONE REVETMENT	S.Y.	771	20.00	15,420.00
140	6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	L.F.	42	4.00	168.00
150	6161005	CONSTRUCTION SIGNS	S.F.	115	14.00	1,610.00
160	6161009	FLAG ASSEMBLY	EACH	2	25.00	50.00
170	6161027	CHANNELIZER (VERTICAL PANEL) WITH LIGHT	EACH	56	56.00	3,136.00
180	6161031	TYPE III MOVEABLE BARRICADE WITH LIGHT	EACH	4	160.00	640.00
190	6181000	MOBILIZATION	L.S.	1	30,000.00	30,000.00
200	6206000C	"4 IN. WHITE WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS"	L.F.	940	1.35	1,269.00
210	6206001C	"4 IN. YELLOW WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS"	L.F.	120	1.35	162.00
220	6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	L.S.	1	5,000.00	5,000.00
320	7250312A	12 IN. PIPE GROUP B	L.F.	26	40.00	1,040.00
330	7320012A	12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	EACH	2	200.00	400.00
340	8051000A	SEEDING - COOL SEASON MIXTURES	ACRE	0.3	13,000.00	3,900.00
350	8061005	ROCK DITCH CHECK	L.F.	90	21.00	1,890.00
		Roadway SUB-TOTAL				159,106.50 EG
360	9031250A	"U-CHANNEL POST, 3 LB"	L.F.	132	13.00	1,716.00 EG
370	9035069A	SHE-FLAT SHEET FLUORESCENT	S.F.	36	24.00	864.00
		Signing SUB-TOTAL				2,580.00
40	2061000	CLASS 1 EXCAVATION	C.Y.	140.00	40.00	5,600.00
50	2065500	TEMPORARY SHORING	L.S.	1	11,000.00	11,000.00
60	2160500	REMOVAL OF BRIDGES	L.S.	1	8,000.00	8,000.00
120	5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	S.Y.	107	75.00	8,025.00
230	7021012	STRUCTURAL STEEL PILES (12 IN.)	L.F.	208	40.00	8,320.00
240	7029902	SETTING PILES IN ROCK	EACH	16	320.00	5,120.00
250	7032003	CLASS B CONCRETE (SUBSTRUCTURE)	C.Y.	84.0	62.00	5,208.00
260	7056055	"27 IN., PRESTRESSED CONCRETE ADJACENT BOX BEAM"	L.F.	372	370.00	137,640.00
270	7101000	REINFORCING STEEL (EPOXY COATED)	LBS	5,580	1.50	8,370.00
280	7111001	WATERPROOFING MEMBRANE	S.Y.	171	100	17,100.00
290	7134000	BRIDGE GUARDRAIL (THREE BEAM)	L.F.	117	160.00	18,720.00
300	7151001	VERTICAL DRAIN AT END BENTS	EACH	2	1,000.00	2,000.00
310	7161000	PLAIN NEOPRENE BEARING PAD	EACH	14	150.00	2,100.00
		Bridge or Retaining Wall SUB-TOTAL				330,155.00
		TOTAL PROJECT				491,841.50

Written Estimate: four hundred ninety one thousand eight hundred forty one ^{50/100}

Contractor: Gershenson Construction Co., INC

Phone: 636-938-9595

Signature: [Signature]

Date: 3-20-18

Name: [Signature]

Edward N. Gershenson
President